



JOB PACK GUIDELINES:

Our distributor and dealer partners may need to package small product quantities from the material units received from the MoistureShield facility. Below are guidelines to help ensure job packs reach the installer in optimal condition.

IMPORTANT TIP: MATERIAL SHOULD ALWAYS BE COVERED PRIOR TO USE


Leave the unit wrap in place until the material is needed, whether at the jobsite, distributor yard, or dealer yard. The wrap will keep the material clean, and help prevent bowing due to sun exposure over time.

1. KEEP IT STABLE


Configure the boards to ensure the bundle is stable during transit. Build layers with uniform board counts when possible to balance the bundle's weight and maximize stability. Use pallet boards for packs with 18 or more boards.



32 Boards or More:
8 boards per layer
Max 6 complete layers



18 to 32 Boards:
4 - 5 boards per layer
Max 6 complete layers



8 - 17 Boards:
Layers of 2 - 3 boards
Max 6 complete layers



Less than 8 Boards:
Single stack

2. KEEP IT TIDY

Remove dirt, rocks, and other debris from each layer before stacking additional boards in the job pack. Coarse materials between the bundle layers can cause surface scratches while stacking and during transit. Wrap the bundle with protective lumber wrap to keep it clean and safe from the elements until installation.



3. KEEP IT SECURE

Place pallet boards the length of the bundle as shown below: 12" from each end, and 22" apart to the center. Apply plastic straps with corner guards at each pallet board, between the pallet boards, and at each end to hold the bundle tight. Flip the top layer of boards face-down to prevent accidental damage while in transit.

